



1, क्वीन्स वे, कोलकाता - 700 071
1, Queen's Way, Kolkata - 700 071

विक्टोरिया मेमोरियल हाल VICTORIA MEMORIAL HALL

(भारत सरकार के संस्कृति मन्त्रालय के प्रशासनिक नियन्त्रण
के तहत एक स्वायत्त संगठन)
(An autonomous organisation under the administrative
control of the Ministry of Culture, Govt. of India)

V.M. No. 2425/VC-06/11

23 December 2017

Notice Inviting Tender

Sealed Tenders are invited by the Victoria memorial Hall from licensed electrical contractors for the work as mentioned below:

Name of Work:

Supply, laying and fixing of 3.5 core, 50 sqmm armoured u/g Aluminium cable from Electrical Switch Room to the 02 no. pump panel box near by East gate of VM garden. (Work Schedule enclosed vide Annexure – 1)

The Sealed tenders addressed to the Administrative Officer, Victoria Memorial Hall, 1 – Queens Way, Kolkata 700071, should be dropped in the tender box kept for the purpose in the office of the undersigned on or **before 3:00 pm on 03.01.18** . The Tenders will be opened on the same day at 4:00 pm in the presence of such tenderers or their representatives who wish to remain present.

Tenders in sealed cover should be superscribed "Supply, laying and fixing of 3.5 core, 50 sqmm armoured u/g Aluminium cable from Electrical Switch Room to the 02 no. pump panel box near by East gate of VM garden, Kolkata."

Rates so quoted will remain valid for six months.

Rates should be quoted inclusive of GST and transportation charges etc. The rate should be quoted both in words and figures. The tenderers should clearly state the delivery schedule.

Tenders should be submitted on the letterhead of the firm.

The tenderers should have sufficient experience in doing similar nature of jobs preferably in Govt. Sector. The tenderers should submit photocopies of their licences, PAN card and papers in support of their work experience.

The tenderers will be required to deposit 2% of the quoted rates as Earnest Money in the form of Demand Drafts in favour of Victoria Memorial Hall, drawn from any commercial bank, payable at Kolkata. The above earnest money will be refunded after one month from the date of issuance of Work Order. The EMD's of unsuccessful tenderers shall be released after the issuance of work order or latest by one month

The successful tenderer will be required to deposit 10% of the total work value as Security Deposit in the same form in which the Earnest money has been deposited to the Trustees of Victoria Memorial before receiving of Work Order. The security money since deposited will



1, क्वीन्स वे, कोलकाता - 700 071
1, Queen's Way, Kolkata - 700 071

विक्टोरिया मेमोरियल हाल VICTORIA MEMORIAL HALL

(भारत सरकार के संस्कृति मन्त्रालय के प्रशासनिक नियन्त्रण
के तहत एक स्वायत्त संगठन)
(An autonomous organisation under the administrative
control of the Ministry of Culture, Govt. of India)

be refunded not earlier than six month from the date of completion of the job. The earnest money will be forfeited if the Security Money is not deposited within two (02) days from the date of intimation in this regard or if the successful tenderer is unable to commence the job within specified time.

The job executed by the successful tenderer shall have to be guaranteed against bad workmanship for a period of six (6) months from the date of completion of the job. If any defect is detected during the period as mentioned above, he will be liable to rectify the same free of cost within reasonable time. Otherwise, VMH will get it rectified at its own cost and adjust the same from the Security Deposit.

The job to be executed is scheduled to be inspected by the concerned unit of the VMH.

The job to be executed will follow the Govt. specification.

The job under reference should be completed within 7 days from the date of receipt of final work order.

For any additional information, tenderers may contact the Electrician (9883224028) of this office between 2:00 pm to 4:00 pm on any working day with prior intimation.

The authority reserves the right to accept or reject any or all the tenders without assigning any reason thereof.

Encl: One Schedule of Work

Administrative officer

Annexure - 1

SCHEDULE OF WORK

Supply, laying and fixing of 3.5 core, 50 sqmm armoured u/g Aluminium cable from Electrical Switch Room to the 02 no. pump panel box near by East gate of VM garden.

Sl. No.	Description	Qty	Rate	Unit	Amount in Rs.
01	Supply & Laying of following size of PVC insulated and PVC sheathed/ XLPE armoured aluminium conductor cable of 1.1 KV grade direct in ground including excavation, sand cushioning, protective covering and refiling the trench etc. as required. 1. 3.5 core, 50 sqmm	150 Mtrs		Mtrs	
02	Providing & fixing 40 mm dia medium class GI pipe ISI marked for cable protection at concrete area and road crossing i/c cutting of concrete pathways and refilling the same making good the damages.	33 Mtrs		Mtrs	
03	Supply and making end termination with brass compression gland and aluminium lug for following size of PVC insulated and PVC sheathed/ XLPE aluminium Conductor cable of 1.1 KV grade as required 1. 03.5 core, 50 sqmm.	02 Sets		Sets	
04	Dismantling and disconnection of existing burnt out / defective main switch and Supply and fixing of new main switch 125 Amps sheet steel housing, type F-N (Cat no. SK90486) make L&T complete with fuse links i/c making 16 swg MS sheet cable and box complete with SITC , as required.	01 Job		01 Job	