

VMNO 518 /2020

Date-17.03.2020

Tender Notice

Victoria Memorial, 1 Queen's Way, Kolkata 700071 (2223-0953) invites tender from the reputed/experienced Govt. contractors having proper work license for construction of 2 nos. ladies toilet at north and south gates of VM campus (as per scope of work enclosed). The tender in sealed cover should be superscribed with "Tender for construction of ladies toilets" must be sent to the Administrative Officer, Victoria Memorial Hall within 02 p.m. on 20.03.2020. The tenders will be opened on the same day at 2.30 p.m. in the office chamber of Administrative Officer. Tenderers/their representatives may remain present at the time of opening of tender if they so desire.

The tender should be accompanied by an earnest money deposit of Rs.2000.00 (Rupees two thousand) only in the form of a Bank draft drawn in the favour of "Victoria Memorial Hall" payable at Kolkata, which is returnable to the unsuccessful bidders latest on or before the 30th day after the award of the contract. Please note that tender without the earnest money will be rejected outright.

Tenderers should submit copies of work license, PAN card, GST certificate already executed work orders of recent period in support of their experience for evaluations.

The rate should be inclusive of all charges i.e. labour, materials, transportation, fitting, fixing and taxes, if any and quoted both in words and figures. The successful tenderer will be required to complete the job within 15 days of the receipt of the order. The work should be done with good quality ISI marked materials under the supervision of the Caretaker.

VMH reserves the right of rejection of any or all tenders without assigning any reason.

Administrative Officer

Name of Work: Construction of ladies toilets at south and north gates VMH Kolkata.			
Item No.	Description of Item	Unit	Quantity
1	Earth work in excavation including filling of excavated earth,	cum	1.00
2	Providing and laying in position cement concrete of 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size)	cum	4.00
3	Providing and laying in position specified grade of 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	cum	2.00
4	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position	Kg	400.00
5	Steel work welded in built up sections/ framed work including cutting, , fixing and applying a priming coat of approved steel primer	Kg	700.00
6	Providing and fixing white vitreous china pedestal type W.C. pan with seat and lid, 10 litre low level white P.V.C. flushing cistern,	each	2.00
7	White Vitreous China Flat back wash basin size 550x400 mm with single 15 mm C.P. brass pillar tap and waste pipe ,connection pipe	each	2.00
8	Providing and fixing 15 mm PTMT bib cock of approved quality and colour.	each	2.00
9	Providing and fixing on wall face un plasticised - PVC moulded Bend 87.5° ,Single tee without door 110 mm	each	8.00
10	Providing and fixing on wall face un plasticised Rigid PVC pipes 110 mm diameter	mtr	20.00
11	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes,		
11a	25 mm nominal outer dia .Pipes.	mtr	12.00
11b	15 mm nominal outer dia. Pipes.	mtr	10.00
12	Providing and fixing 15 mm PTMT stop cock	each	2.00
13	Providing corrugated (polymer coated) G.S. sheet roofing including surface fixed with J or L hooks,	sqmt	10.00
14	Providing and fixing Base frame work for ACP wall under the relevant aluminium items. Including necessary item	sqmt	75.00
15	Providing and laying Ceramic glazed floor tiles of size 300x300 mm	sqmt	16.00
16	Providing and fixing factory made P.V.C. door frame of size 50x47 mm with a wall thickness of	mtr	5.00
17	Providing and fixing to existing door frames. 30 mm thick Glass Fibre Reinforced Plastic (FRP) panelled door shutter.	sqmt	2.00