



1. क्वीन्स वे, कोलकाता - 700 071
1. Queen's Way, Kolkata - 700 071

विक्टोरिया मेमोरियल हाल
VICTORIA MEMORIAL HALL
(भारत सरकार के संस्कृति मंत्रालय के प्रशासनिक नियंत्रण
के तहत एक स्वायत्त संगठन)
(An autonomous organisation under the administrative control
of the Ministry of Culture, Govt. of India)

VM no. 1153 /2020

Date: 7.12.20,

Tender notice

Victoria Memorial Hall, 1 Queens Way, Kolkata 700071 (2223-0953) invites tender from the reputed/experienced Govt contractors having proper work license for repairing of boundary wall (Balustrade) of Victoria Memorial Hall on the Western side, damaged due to Umphun cyclone. The tender in sealed cover should be superscribed with "Tender for repairing of boundary wall" must be sent to the office of the Secretary & Curator, Victoria Memorial Hall within 01 p.m. on 15.12.2020.

The tender should be accompanied by an earnest money deposit of Rs.2000.00 in the form of Bank draft drawn in favour of 'Victoria Memorial Hall' payable at Kolkata, which is returnable to the unsuccessful bidders latest on or before the 30th day after the award of the contract. Please note that tender without the earnest money will be rejected outright.

The rate should be inclusive of all charges i.e. labour, materials, transportation, fitting, fixing and taxes, if any and quoted both in words and figures. The successful tenderer will be required to complete the job within 15 days of the receipt of the order. The work should be done (as per scope of work) with good quality ISI marked materials under the supervision of the Caretaker.

VMH reserves the right of rejection of any or all tenders without assigning any reason.

Copy forwarded:

Sri Dipankar Samanta. He is requested to get the matter published on VM website.
The Caretaker, VMH.

Secretary & Curator

Secretary & Curator

☎ : 2223-1890 / 1891/0953/5142 • फैक्स / Fax : +91-33-2223-5142

ई-मेल / E-Mail : Victomem@gmail.com • वेबसाइट / Website:www.victoriameorial-cal.org

Scope of work

Name of work: Repair to damage boundary wall (Balustrade) at Western side of VMH, Kolkata

Sl. No.	Item Description	unit	Qty.
1.	Dismantling of cement concrete mortar and brick work with disposal.	cum	4 cum
2.	Earth cutting	Cum	1 cum
3.	Cement concrete 1:4:10 (1 cement, 4 sand, & 10 stone chips for foundation	Cum	0.5 cum
4.	Cement concrete 1:2:4 (1 cement, 2 sand, 4 stone chips) for Balustrade boundary wall concreting with centering, shuttering complete.	Cum	2 cum
5.	Brick work (First class bricks)	Cum	1 cum
6.	Plastering (1:6) (1 cement, 6 sand) ornamental design plastering.	Sqm	7 sqm
7.	Finishing weather coat best quality (exterior paint) as per existing shade.	Sqm	7 sqm
8.	Fitting and fixing RCC Baluster existing shape and size	Each	23 each