



1. क्वीन्स वे, कोलकाता - 700 071  
1. Queen's Way, Kolkata - 700 071

# विक्टोरिया मेमोरियल हल VICTORIA MEMORIAL HALL

(भारत सरकार के संस्कृति मंत्रालय के प्रशासनिक नियंत्रण  
के तहत एक स्वायत्त संगठन)  
(An autonomous organisation under the administrative control  
of the Ministry of Culture, Govt. of India)

VM No. 1686/VA-19/2002(Part-1)

Date: 14.12.2022

## Notice Inviting Tender

Sealed Tenders are invited by the Victoria memorial Hall from licensed electrical contractors for the work as mentioned below:

### Name of Work:

“Supply, laying and commissioning of 25 Sqmm Al. Armoured cable from Feeder Box no. 01 of building illumination to Pump Room nearby South Gate of VM building.”.  
(Schedule of Work enclosed vide Annexure – 1)

The Sealed tenders addressed to the Secretary & Curator, Victoria Memorial Hall, 1 – Queens Way, Kolkata 700071, should be dropped in the tender box kept for the purpose in the office of the undersigned on or before 2:00 pm on 30/12/2022. The Tenders will be opened on the same day at 2:30 pm in the presence of such tenderers or their representatives who wish to remain present.

Tenders in sealed cover should be superscribed “Supply, laying and commissioning of 25 Sqmm Al. Armoured cable from Feeder Box no. 01 of building illumination to Pump Room nearby South Gate of VM building”.

Rates so quoted will remain valid for six months.

Rates should be quoted inclusive of taxes (mentioning the tax rate) and transportation charges etc. The rate should be quoted both in words and figures. The tenderers should clearly state the delivery schedule. The job should be completed within 10 days from the date of receipt of Work Order.

Tenders should be submitted on the letterhead of the firm.

The tenderers should have sufficient experience in doing similar nature of jobs preferably in Govt. Sector. The tenderers should submit photocopies of their licences, PAN card, GSTIN (GSTR-1, GSTR-3B) documents and papers in support of their work experience.

The tenderers excepting those who are exempted from furnishing EMD as per G.O.I. Order (photo copy to be furnished) will be required to deposit 2% of the quoted rates as Earnest Money in the form of Demand Drafts in favour of the “Victoria Memorial Hall”, drawn from any commercial bank, payable at Kolkata. The above earnest money will be refunded after one month from the date of issuance of Work Order. The EMD's of unsuccessful tenderers shall be released after the issuance of work order or latest by one month.

☎ : 2223-1890 / 1891/0953/5142 • फैक्स / Fax : +91-33-2223-5142

ई-मेल / E-Mail : Victomem@gmail.com • वेबसाइट / Website: www.victoriameorial-cal.org



1. क्वीन्स वे, कोलकाता - 700 071  
1. Queen's Way, Kolkata - 700 071

# विक्टोरिया मेमोरियल हाल VICTORIA MEMORIAL HALL

(भारत सरकार के संस्कृति मंत्रालय के प्रशासनिक नियंत्रण  
के तहत एक स्वायत्त संगठन)

(An autonomous organisation under the administrative control  
of the Ministry of Culture, Govt. of India)

The successful tenderer will be required to deposit 3% of the total work value as Security Deposit in the same form in which the Earnest money has been deposited to

the Victoria Memorial Hall before receiving of Work Order. The security money since deposited will be refunded not earlier than eight months from the date of completion of the job. The earnest money will be forfeited if the Security Money is not deposited within seven days from the date of intimation in this regard or if the successful tenderer is unable to commence the job within specified time.

The job executed by the successful tenderer shall have to be guaranteed against bad workmanship for a period of six (6) months from the date of completion of the job. If any defect is detected during the period as mentioned above, he will be liable to rectify the same free of cost within reasonable time. Otherwise, VMH will get it rectified at its own cost and adjust the same from the Security Deposit.

The job to be executed is scheduled to be inspected by the concerned unit of the VMH.

The job to be executed will follow the Govt. specification.

For any additional information, tenderers may contact the In-charge Electric Unit of this office between 2:00 pm to 4:00 pm on any working day.

The authority reserves the right to accept or reject any or all the tenders without assigning any reason thereof.

Encl: One Schedule of Work

  
Secretary & Curator

Copies along with Schedules of Work forwarded to the Security Officer for kind information and Shri Dipankar Samantha with request to insert the NIT in our website .

  
Secretary & Curator

☎ : 2223-1890 / 1891/0953/5142 • फैक्स / Fax : +91-33-2223-5142

ई-मेल / E-Mail : Victomem@gmail.com • वेबसाइट / Website: www.victoriamemorial-cal.org



ANNEXURE - 1

Schedule of Work

Name of Work: Supply, laying and commissioning of 25 Sqmm Al. Armoured cable from Feeder Box no. 01 of building illumination to Pump Room nearby South Gate of VM building .

Sl. No.	Description	Qty	Rate	Unit	Amount
01	Supplying, Laying & Commissioning of PVC insulated and sheathed/ XLPE power cable of 1.1 KV grade (make Havells/ Polycab/ Gloster) direct in ground i/c excavation, protective covering (without sand cushioning) and refilling the trench etc, as required. a. 2 Core, 25 sqmm,	65 mtrs		Mtr	
02	Supply and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed/ XLPE Aluminium conductor cable of 1.1 KV grade, as required. a. 2 Core, 25 sqmm,	02 Sets		Set	
04	Supply and laying of 2.5 sqmm, 03 core insulated sheathed flexible copper cable in existing SP Distribution box to Motor Starter to Pump motor appropriate length by PVC pipe direct on surface, as required.	10 Mtrs		Mtrs	
05	Providing and fixing 50 mm dia medium class GI pipe ISI marked for cable protection at road crossing including cutting and refilling the same making good the damages	18 Mtrs		Mtrs	
06	Supply and fixing of 8 way SPN DB in sheet steel enclosure (single door) for pump room.	01		Job	
07	Supply and fixing 220/ 440 Volt of following Amps DP/ SP MCB DP MCB complete with connection testing and commissioning etc in the existing 8 way SPN DB, asrequired. a. 63 Amps DP Isolator b. 25 Amps, DP MCB c. 5 – 32 SP MCB	01 02 02		No. Nos. Nos.	