



1, क्वीन्स वे, कोलकाता - 700 071
1, Queen's Way, Kolkata - 700 071

विक्टोरिया मेमोरियल हॉल

VICTORIA MEMORIAL HALL

(भारत सरकार के संस्कृति मंत्रालय के प्रशासनिक नियंत्रण के तहत एक स्वायत्त संगठन)

(An autonomous organisation under the administrative control of the Ministry of Culture, Govt. of India)

VM No. 1314

/VA-19/2002

Date: 30.9.22

Notice Inviting Tender

Sealed tenders are invited by the Victoria Memorial Hall from experienced and reputed Govt. contractors for the work as mentioned in the enclosed schedule of work:

The Sealed tenders addressed to the Secretary & Curator, Victoria Memorial Hall, 1, Queens Way, Kolkata - 71 should be dropped in the tender box kept for the purpose in the Administrative Block of Victoria Memorial Hall, Kolkata, on or before 3:00 pm on 12.10.2022 which will be opened on the same day in the presence of such tenderers or their representatives who wish to remain present at 3:30 pm

The tender in sealed cover should be superscribed "Tender for Surging of 01 (one) no. of existing tube well at VMH garden (Deodar lane), Kolkata"

The rate so quoted will remain valid for six months.

The rate should be quoted inclusive of all charges and taxes i.e. GST, transportation and cost of parts to be required etc. The rate should be quoted both in words and figures. The tenderers should clearly state the delivery schedule.

The tender should be submitted on the letterhead of the firm.

The tenderer should have sufficient experience in doing similar nature of jobs preferably in Govt. Sector. The tenderer should submit photocopies of his license and papers in support of his work experience. Photo copies of PAN Card and GST certificate are also to be submitted.

The successful tenderer will be required to deposit 10% of the total work value as Security Deposit in the form of Demand Draft in favour of the Victoria Memorial Hall, payable at Kolkata before issuance of Work Order.

☎ : 2223-1890/1891/0953/5142 • फैक्स/Fax : +91-33-2223-5142

ई-मेल/E-mail : victomem@gmail.com • वेबसाइट/Website : www.victoriame-morial-cal.org



1, क्वीन्स वे, कोलकाता - 700 071
1, Queen's Way, Kolkata - 700 071

विक्टोरिया मेमोरियल हॉल

VICTORIA MEMORIAL HALL

(भारत सरकार के संस्कृति मंत्रालय के प्रशासनिक नियंत्रण
के तहत एक स्वायत्त संगठन)

(An autonomous organisation under the administrative control
of the Ministry of Culture, Govt. of India)

The successful tenderer will be required to complete the allotted job within 15 days from the date of receipt of the Work Order failing which their SD shall be liable to be forfeited without any further intimation.


The job executed by the successful tenderer shall be guaranteed against bad workmanship for a period of six (6) months from the date of completion of the job. If any defect during the period as mentioned above is detected, he will be liable to rectify the same free of cost within reasonable time.

The job to be executed is scheduled to be inspected by the concerned unit of the VMH.

The job to be executed will follow the Govt. specification.

For any additional information, tenderers may contact the Electrician (9883224028) of this office between 2:00 pm to 4:00 pm on any working day.

The authority reserves the right to accept or reject any or all the tenders without assigning any reason thereof.


(Dr. Jayanta Sengupta)
Secretary & Curator

Copy forwarded to AO, SO and Shri Dipankar Samanta with request to insert the NIT in our website.

Dr.

Schedule of Work

Name of Work:: Surging of 01 (one) no. of existing tube well at VMH garden (Deodar lane).

Sl. No	Description of items	Unit	Qty	Rate (Rs.)	Amount (Rs.)
01	Labour for lifting of existing submersible pump motor set assembly from the tube well prior to the washing operation of the tube well by using tripod or other suitable means i/c hiring of all tools and plant complete. The items including servicing of old submersible pump motor set fitting, clamping, pump hanging pipe including threading, jointing, repairing and lower the same by suitable method including preparation of bed complete in all respect by proper functioning of the tube well .	Job	01		
2	Labour charge for measuring depth of the existing tube well prior to washing and development and final depth to ensure the cleanliness of strainer and removal of deposited sediments complete by means of necessary measuring tools	Job	01		
3	Surging of existing tube well with necessary chemical treatment and bucket washing and by use of high speed diesel air compressor machine and developing the tube well till the yield is obtained at least by 75% of the total specified yield of the tube well and draw down is within the permissible limit of 10% variation and water so obtained after such washing and developing will be free from sand and other solid impurities. The rate is inclusive of all labour and materials, necessary fuel for compressor machine etc., hiring charge of tools and plants and cost of the machineries . For tube well of approx 150m depth out of which 150 mm dia up to a depth of approx 35 m and rest is of 100 mm dia.	Job	01		
4	Disposal of rubbish, unserviceable dismantled material by mechanical transport including loading, unloading and disposal the material at disposal area outside the VMH premises and complete.	Job	01		
	Total				

RF